

PROJECT INFORMATION SHEET

April 20, 2006

PROJECT NAME	Briarcliff Road at North Druid Hills Road Intersection Improvements	COUNTY	DeKalb
DESCRIPTION	Intersection improvements at North Druid Hills Road and Briarcliff Road		

GENERAL INFORMATION

LENGTH	0.95 MILES
SPEED DESIGN	35 MPH
PROPOSED TYPICAL SECTION	Widen North Druid Hills Road to provide a new westbound through lane and a center TWLTL ⁽¹⁾ . Widen Briarcliff Road to provide new southbound through lane.
PROPOSED R/W	VARIES 60 FT – 125 FT
EXISTING R/W	VARIES 60 FT – 125 FT
DISPLACEMENTS	NONE
WETLANDS	NONE
HISTORICAL IMPACTS	NONE

DESIGN TRAFFIC 2004 ADT⁽²⁾	Briarcliff Road – 23,035 vpd ⁽³⁾ North Druid Hills Road – 58,048 vpd
2016 ADT	Briarcliff Road – 29,200 vpd North Druid Hills Road – 74,100 vpd
TRAFFIC SIGNAL	A modification of the existing signal will be necessary. The pole in the northwest quadrant will be relocated.

ESTIMATED COSTS

FUNDING SOURCE	2005 Bond Program
CONSTRUCTION	\$1,700,000
RIGHT-OF-WAY	\$500,000

SCHEDULE

PUBLIC INFORMATION MEETING	April 20, 2006
LENGTH OF CONSTRUCTION	6 Months
CONSTRUCTION START	March 2007

(1) TWLTL = Two-way left-turn lane

(2) ADT = Average Daily Traffic

(3) vpd = vehicles per day